



**GENERAL NOTES**

- A 4' TALL MESH, SNOW, OR CHAIN LINK FENCE SHALL BE INSTALLED AND MAINTAINED THROUGHOUT THE PROJECT DURATION. MESH AND SNOW FENCING SHALL BE SECURED TO WOOD OR METAL POSTS SPACED NO MORE THAN 6' APART.
- DISTANCE BETWEEN INSTALLED FENCE AND TREE TRUNK SHALL BE DETERMINED BY THE DIAMETER AT BREAST HEIGHT (DBH). EVERY INCH OF DBH SHALL EQUATE TO 1' OF SPACING BETWEEN THE TRUNK AND FENCE (DBH = 4.5' ABOVE GROUND LEVEL).
- FENCING SHALL BE SECURED WITH A MINIMUM OF 4 WIRE TIES AT EACH STAKE/POST.
- ALL FENCING SHALL REMAIN UPRIGHT THROUGHOUT THE DURATION OF THE PROJECT.

REVISION: 1/1/20



VILLAGE OF RIVER FOREST  
 PUBLIC WORKS - ENGINEERING  
 400 PARK AVE.  
 RIVER FOREST, IL 60305  
 PH. (708)-366-8500

# PARKWAY TREE PROTECTION DETAIL